

S-Series Technical Specifications





Product Description:

24/7 OSC "S-Series" units are designed to meet the rugged demands of the construction site rental market. The "S-Series" units have over 10 years of Mobile Camera System manufacturing built into them. Each system is designed for easy deployment, 24/7 usage, advanced analytics and with the highest quality high mega pixel cameras. Each unit is designed to be self sufficient and self report any technical problems it may experience. These machines have changed the industry standard for Mobile Camera system deployment.

Product Features:

- Industrial Rental rugged design
- Easy to deploy
- Advanced analytics
- Onboard Redundant hard drive storage
- 1,380W of solar
- 2000amp/hr of AGM Storage batteries
- Hydraulic Mast
- 25' Mast height
- Onboard "monitoring ready" analytics
- 4G LTE Cellular router
- 3MP PTZ cameras w/30 x zoom
- Talk down feature

Applications:

Industrial, Manufacturing, Construction Entertainment State and Federal Law Enforcement DOT's, Traffic monitoring FEMA, TSA, Emergency management Oil and Gas Colleges/Universities

Specifications:

Stowed: 176.4"(14' 7") L x 82.8"(6'9") W x 113"(9'4") H **Deployed:** 176.4"(14'7") L x 141"(11.75") W x 295"(24'6") H

Weight: 4,280lbs
Outriggers: Adjustable

Hitch: 2" ball Axles: 2

Breaking System: Surge Parking Break: Manual w/chocks

Solar Array: 4 x Panasonic N325 panels (2 x slide out trays) **Solar Controller**: Victron SmartSolar 100amp MPPT Controller

Cameras: 4 x 3MP IP 30x Zoom

Camera: Look down on panels 1 x 1080P fixed eyeball Nighttime Lighting: 4 x 300' IR Illuminators w/photocell Offsite Remote Controls: Auto ping 8 point controller

- 1 Router-auto ping with auto reboot if ping fails
- 2 Cameras with remote on/off
- 3 IR Illuminators with remote on/off
- 4 NVR with remote on/off
- 5 Strobes with remote on/off
- 6 Analytics device with Remote on/off
- 7 Network switch with remote on/off
- 8 Spare

Batteries: 8 x 250amp/hr AGM batteries **Connection:** Cellular Router 4G LTE

Low Voltage Disconnect: BG-40 with auto reconnect

Control Housing: Lockable

Equipment Panel: Thermostatically controlled fan

Mast Cable: Molded Spiral Nycoil Talk Down: Valcom Speaker Strobes: Red/Blue LED w/photocell

NVR: 8Ch with 4TB HDD

Analytics: Checkvideo CV4IP with 6TB HDD

Voltage regulator: Victron Energy Isolated AC/DC Converter

Operating Voltage: 12V

Inverter Voltage: MorningStar SureSine-300 Inverter Input 12V Output: 115vac

Land power charging: lota 55amp IQ Smart charger